	Basic Rate	46.40								
	Add Area Weightage 8%	3.71								
	Total	**50.11**								
8	KSRB 4.1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2013-14)	Cum								
	12th cross		1	160.00	0.45	0.15	10.80		4211.38	0.00
	Basic Rate	3973.00								
	Add Area Weightage 6%	238.38								
	Total	**4211.38**								
9	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2013-14)	Cum								
	12th cross		1	180.00	0.45	0.10	8.10			
	Kerb stone joints		1	130.00	0.45	0.10	5.85			
							13.95		4690.50	**65432.00**
	Basic Rate	4425.00								
	Add Area Weightage 6%	265.50								
	Total	**4690.50**								
10	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 28/ Item No.5.33/ PWD SR 2013-14	**Sqm**								
			Qty Vide Iteam No 7				97.20			
							97.20		70.04	**6808.00**
	Basic Rate	64.85								
	Add Area Weightage 8%	5.19								
	Total	**70.04**								
11	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 27 I. 5.31.1) Page No. 28/ Item No. 5.31/ PWD SR 2013-14	**Sqm**								
	12th cross		1	180.00	-	0.90	**162.00**			
			Deduct Availabe Qty Vide Iteam No 7				**97.20**			
							64.80		343.44	**22255.**
	Basic Rate	318.00								
	Area Weightage 8%	25.44								
	Total	**343.44**								
12	Providing & fixing pre cast solid concrete Kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete of size 450x20x400 mm Page No. 28/ Item NO 5.29/1, PWD SR 2013-14	**No**								
	19th cross both side									
	120/.45=		2	268.00			536.00		**316.44**	**169612**